



ROAD DESIGN - CHAINAGES 345 TO 700

CHAINAGE	EXISTING SURFACE	DESIGN LINE GRADING	VERTICAL GEOMETRY	HORIZONTAL GEOMETRY
345	120.524	120.365	0.301%	
360	120.538	120.41		
380	120.581	120.47		
400	120.663	120.53		
420	120.756	120.65		
440	120.704	120.507	-0.477%	
460	120.721	120.411		
480	120.756	120.316		
500	120.78	120.221		
513	120.77	120.159		
520	120.762	120.185		
540	120.764	120.259	0.372%	
560	120.746	120.408		
584	120.739	120.423		
600	120.743	120.369		
620	120.717	120.303	-0.333%	
640	120.703	120.236		
644	120.706	120.223		
660	120.742	120.281		
680	120.763	120.355		
686.5	120.781	120.379		
700	120.818	120.41		35.00m V.C.

LONGITUDINAL SECTION - CONTROL STRING CL OF ROAD DESIGN

HORIZONTAL SCALE 1:500 (A1)
VERTICAL SCALE 1:50 (A1)

- NOTES**
- CONTRACTOR TO CONFIRM DEPTH AND LOCATION OF EXISTING SERVICES PRIOR TO EXCAVATION AND ORDERING MATERIALS.
 - DO NOT SCALE OFF DRAWINGS. DRAWINGS ARE FOR ENGINEERING PURPOSES ONLY. REFER TO ARCHITECTURALS FOR SETOUT OF BUILDING AND RELEVANT REGULATORY PLANS FOR RELEVANT INFORMATION.
 - ALL EARTHWORKS TO COMPLY WITH AS3798.
 - ALL DRAINAGE AND PLUMBING WORKS TO COMPLY WITH AS3500.
 - LEVELS ARE FINISHED PAVEMENT LEVELS AND NOT TOP OF KERB UNLESS NOTED OTHERWISE.
 - BATTER TREATMENT TO BE TOPSOIL AND SEED IN LOCATION OF DISTURBANCE.
 - ENSURE PROPERTY DRAINAGE IS TO BE MAINTAINED TO NEW SWALE.
 - WHERE NATURE STRIP IS BEEN FILL REMOVE HEADWALL AND PIPES.

LEGEND

MARK	ITEM	MARK	ITEM	MARK	ITEM
	PROPOSED 2 COAT BITUMEN PAVING REFER TO DETAIL A		PROPOSED STORMWATER SIDE ENTRY PIT REFER TO DETAIL SEPI		EXISTING STORMWATER HEADWALL
	PROPOSED CONCRETE DRIVEWAY REFER TO DETAIL B		PROPOSED STORMWATER PIT REFER TO DETAIL SWP		EXISTING WATER MAIN EXACT LOCATION AND DEPTH TO BE CONFIRMED ON SITE
	EXISTING BUILDING		PROPOSED MAJOR CONTOURS AT 1.00m INCREMENTS		EXISTING TELSTRA LINE EXACT LOCATION AND DEPTH TO BE CONFIRMED ON SITE
	PROPOSED KERB AND GUTTER REFER TO DETAIL KG		PROPOSED MINOR CONTOURS AT 0.20m INCREMENTS		EXISTING OVERHEAD ELECTRICAL LINE

ISSUED FOR TENDER



No.	DATE	DETAILS	BY
J	19.04.2021	ISSUED FOR TENDER	C.A
I	13.04.2021	KERB REVISED	C.A
H	09.04.2021	UPDATE KERB AND GUTTER	C.A
G	01.02.2021	MC APPROVED STAMP ADDED	C.A

XEROS PICCOLO CONSULTING ENGINEERS
 5 BYE STREET WAGGA WAGGA, NSW, 2650
 P (02) 6925 5855 F (02) 6925 5655
 E WAGGA@XEROSPICCOLO.COM.AU
 A.C.N. 137 881 853

Project: **PROPOSED ROAD RECONSTRUCTION BENCUBBIN AVENUE COLEAMBALLY NSW 2707**

Sheet Title: ROAD DESIGN LAYOUT PLAN 2/5	Client: MURRUMBIDGEE COUNCIL	Project Number: 190429
Scale: 1:500 (A1) 1:1000 (A3)	Approved:	Sheet Number: B1002
Design: A.X	Drawn: J.G	Revision Number: J
Date: JUNE 2019		